

15-081-00340-0000

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS

RECEIVED
JUN 13 1969
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Casey of J.M. Huber has this

date requested permission to plug the following described well:

Mr. Casey guarantees payment of the plugging fee.

Operator's full Name: J.M. Huber Corporation

Complete Address: Box 911, Amarillo, Texas

Lease Name: Kells Well No. 1

Location: App Center Sec. 29 Twp. 27 Rge. 33 (E) (W)

County Haskell Total Depth 2739' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Casey was instructed to plug the well as follows:

8 5/8" to 616' circulated w/cement. 5 1/2" to 2724' circulated w/cement.
No perforations, 15' of open Hole, Plug bottom w/ Bridge plug at 2700'.
Mud 2700' to 580' Spot 15 sacks cement 580' to 460'
Mud 460' to 120' Spot 15 sacks cement 120' to 0'.

Very truly yours,

Edgar J. Evers
Conservation Division Agent