

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

SEP 1 1 1973

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Lahar of Davies & Fitzgerald has this

date requested permission to plug the following described well:

Mr. Lahar guarantees payment of the plugging fee.

Operator's full Name: Davies & Fitzgerald

Complete Address: 1303 Philtower Bldg., Tulsa, Oklahoma

Lease Name: Barngrover Well No. 1  
C-NE-NE-NW

Location: 330' FNL & 330' FEL NW Sec. 35 Twp. 27 Rge. 24 (E) (W)

County: Ford Total Depth 5091' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Lahar was instructed to plug the well as follows:


8 5/8" to 410' circulated w/ cement. Mud 5091' to 2750'

Spot 70 sacks cement 2750' to 2550' Mud 2550' to 410'

Spot 35 sacks cement 410' to 310' Mud 310' to 45'

Plug, H<sub>11</sub>ls & 15 sacks cement.

Very truly yours,

  
Conservation Division Agent