

To: 1 040672 : 7-30  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION of C SW NE, SEC. 31, T. 27 S, R. 18 W/EX  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-097-20,647-0000 237P  
300' N & 120' E  
SEC. 31, T. 27 S, R. 18 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5118  
Operator: TGT Petroleum Corp.  
Name & Address 209 E. William, Ste. 615  
Wichita, KS 67202

3600 feet from S section line  
1860 feet from E section line  
Lease Name Rice "D" Well # 2  
County Kiowa 162.50  
Well Total Depth 5000 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 360

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address P.O. Box 506, Chase, KS

Company to plug at: Hour: 9:20 a.m. Day: 30 Month: 7 Year: 19 92

Plugging proposal received from Eldon Folmsbee  
(company name) TGT Petroleum (phone) 316-262-6489

were: 4 1/2" at 4855' w/275 sx cement, PBDT 4831', Perfs at 4781-87'  
1st plug sand back to 4780' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.  
hulls, and 150 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 10 a.m. Day: 30 Month: 7 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4718' and dumped 4 sx cement on top of sand through bailer,  
2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 150 sx cement. Maximum pressure 450 psi and shut in 300 psi.

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2529' of 4 1/2" casing AUG 4 1992  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
(old) ~~observed~~ observe this plugging.

DATE 8-10-92  
INV. NO. 35921

Signed Stephen J. Pfeifer  
(TECHNICIAN)

CONSERVATION DIVISION  
Wichita, Kansas