

To: 1090359 #11-19  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION 40' S of C NW SW SEC. 30, T 27 S, R 18 W/EX  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 097-20,678-0000  
1940 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5118  
Operator: TGT Petroleum Corporation  
Name: TGT  
Address: 155 N. Market, Ste. 820  
Wichita, KS 67202

Lease Name Einsel D Well # 1  
County Kiowa  
Well Total Depth 4851 157.66 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 366

Abandoned Oil Well  Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:40 a.m. Day: 19 Month: 11 Year: 19 93

Plugging proposal received from Manny Boatwright  
(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 4851' w/270 sx cement, PBD 4250'; Perfs at 4216-20, 4221-23, 4381-83!  
Bridge plug set at 4423'

1st plug sand back to 4160' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8"  
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 12:30 p.m. Day: 19 Month: 11 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4160' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"  
wiper plug and pumped 150 sx cement.

Maximum pressure 400 psi and shut in 225 psi.


RECEIVED  
STATE CORPORATION COMMISSION

NOV 23 1993

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2560' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

INVOICED  
DATE 12-8-93  
INV. NO. 39430

Signed  (TECHNICIAN)