

11-25-87

To: 1 040019
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill completion date 12/13/80
C NW NW, SEC. 27, T 27 S, R 17 W/E
4620 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 9339
Operator: K & K Oil Company
Name & Address: Box 176
Chase, KS 67524

Lease Name B-S Well # 1-27
County Kiowa 154.86
Well Total Depth 4765 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 410

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2:15 p.m. Day: 25 Month: 11 Year: 19 87

Plugging proposal received from Clay Duntz

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 4745' PBT 4720' Perfs at 4670-88' Elevation 2152'

1st plug pump 15 sx hulls and 20 sx cement,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, release 8 5/8" wiper plug,

and pump 1 sx hulls and 100 sx cement.

Plugging Proposal Received by Dick Kapp (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:45 p.m. Day: 25 Month: 11 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped down 5 1/2" with 100 lbs. hulls and 20 sx common cement,

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 100-800 psi and shut in 350 psi.

DEC 2 1987
12-2-87
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement and 60/40 Pozmix 6% gel by Allied. Recovered 3562' 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (Name) observe this plugging.

DATE 12-4-87

INV. NO. 19116

Signed Stephen J. Pfeifer (TECHNICIAN)