

11-25-87

1 040018

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill completion date 7/10/80

C NE NE, SEC. 28, T 27 S, R 17 W/X
4620 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9339

Lease Name Grimm-Corbel Well # 1-28

Operator: K & K Oil Company

County Kiowa 153.21

Name & Address Box 176

Well Total Depth 4714 feet

Chase, KS 67524

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 408

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:15 p.m. Day: 25 Month: 11 Year: 19 87

Plugging proposal received from Clay Duntz

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 4706' PBD 4706' Open Hole

1st plug sand back to 4656' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1:40 p.m. Day: 25 Month: 11 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4656' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" surface casing with 400 lbs. hulls, 15 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement

Pumping pressure 50-800 psi and shut in 250 psi.

RECEIVED
STATE CORPORATION COMMISSION
DEC 2 1987

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3100' of 5 1/2" casing

(If additional description is necessary, use BACK of this form.)

INVOICED

(If you observe this plugging.

DATE 12-4-87

Signed Stephen J. Pfeifer (TECHNICIAN)

WV. NO. 19114