

1080232

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-20,853-0000

C SE SE, SEC. 28, T 27 S, R 17 W/X
660 feet from N SE Corner of
660 feet from W SE Corner of
NXX section line
WXX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5021

Lease Name Parmley Well # 1-28

Operator: Imperial Oil Co.

County Kiowa

Name & Address: 720 Fourth Financial Center
Wichita, KS 67202

Well Total Depth 4780 155.35 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 405

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:00 pm Day: 9 Month: October Year: 19 84

Plugging proposal received from Joe Maize

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 4779' PBD 4757' Perfs 4674-77' 4683-4703'

1st plug sand back to 4620' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls,
release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by J. H. Metz
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:20 pm Day: 9 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 4779' PBD 4757' Perfs 4674-77' and 4683-4703'

1st plug sanded back to 4620' and dumped 4 sx cement on top of sand through bailer,

2nd plug squeezed well with 3 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls,
released 8 5/8" rubber plug and pumped 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Maximum pressure 700# and shut in pressure 400 psi

OCT 17 1984
10-17-84

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton. Recovered 3536' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

(old / check) observe this plugging.

INVOICED

Signed J. H. Metz
(TECHNICIAN) SQ

DATE 10-18-84

INV. NO. 4396