

To: 1 090498  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-  
150' NW of  
C SE NE, SEC. 2, T 27 S, R 18 W/EX  
3406 feet from S section line  
766 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30606

Lease Name Haney Well # 1-2

Operator: Murfin Drilling Co., Inc.  
Name & Address: 250 N. Water, Ste. 300  
Wichita, KS 67202

County Kiowa  
Well Total Depth 4797 155.90 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 355

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well  D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mike's Salvage License Number 31529

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 8 a.m. Day: 3 Month: 11 Year: 19 94

Plugging proposal received from Vernon Duntz Jr.

(company name) Mike's Salvage (phone) 316-938-2943

were: 4 1/2" at 4790' w/175 sx cement, PBTB 4758', Perfs at 4617-25'

1st plug sand back to 4550' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 9 a.m. Day: 3 Month: 11 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 4550' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 600 psi and shut in 0 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2500' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED Observe this plugging.

DATE 4-30-94 12-1-94

INV. NO. 41770

Signed \_\_\_\_\_ (TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 07 1994  
CONSERVATION DIVISION  
WICHITA, KANSAS