

12-22-87

To: 1 070489
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-097-21,256-0000

SW SE SW, SEC. 35, T 27 S, R 17 W EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 3536

Operator: Ramco Drilling Services, Inc.

Name & Address Box 99

Belpre, OH 45714

330 feet from S section line

3630 feet from E section line

Lease Name Norma Kendall Well # 1

County Kiowa 156.75

Well Total Depth 4823 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 291

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 6 a.m. Day: 22 Month: 12 Year: 19 87

Plugging proposal received from Pat Wagonner

(company name) Red Tiger Drilling Company (phone) 316-263-2371

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2128' Anhydrite 850'

1st plug at 1400' with 50 sx cement, 2nd plug at 660' with 50 sx cement, RECEIVED

3rd plug at 300' with 40 sx cement, 4th plug at 40-0' with 10 sx cement, CONSERVATION COMMISSION

5th plug to circulate rathole with 15 sx cement. DEC 20 1987

12-29-87
Wichita, Kansas

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 7:45 a.m. Day: 22 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1400' with 50 sx cement,

2nd plug at 660' with 50 sx cement,

3rd plug at 300' with 40 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(if additional description is necessary, use BACK of this form.)

INVOICED

(do not) observe this plugging.

DATE 1-7-88

Signed Dan Jordan (TECHNICIAN)

INV. NO. 19411

12-22

NOTICE OF INTENTION TO DRILL

Expected Spud Date. Dec. 11 1987 (see rules on reverse side) API Number 15- 097-21,256

OPERATOR: License # 3536 SW SE SW Sec. 35 Twp. 27S S. Rg. 17 East X West
Name: RAMCO Drilling Services, Inc.
Address: Box 99
City/State/Zip: Belpre, Ohio 45714
Contact Person: Bob Williamson/Dave Gocke
Phone: 614-523-9591

CONTRACTOR: License # 5302
Name: Red Tiger Drilling Company
City/State: 125 N. Market, Suite 1720, Wichita, Kansas 67202
Well Drilled For: X Oil, Storage, Infield, Mud Rotary, Gas, Inj, Pool Ext, Air Rotary, OWWO, Expl, Wildcat, Cable
Well Class: X Infield
Type Equipment: X Mud Rotary

If OWWO: old well info as follows:
Operator:
Well Name:
Comp Date: Old Total Depth:
Nearest lease or unit boundary line: 330 feet
County: Kiowa
Lease Name: Norma Kendall Well #: 1
Ground surface elevation: 2128 feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water: 230
Depth to bottom of usable water: 150
Surface pipe by Alternate: 1 X 2
Surface pipe planned to be set: n/a
Conductor pipe required: 4900
Projected Total Depth: 4900 feet
Formation: Mississippian

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date: 12-9-87 Signature of Operator or Agent: Jean [Signature] Title: Agent

For KCC Use:
Conductor Pipe Required: feet; Minimum Surface Pipe Required: 250 feet per Alt. 1
This Authorization Expires: 12-10-88 Approved By: Pat 12-10-87
EFFECTIVE DATE: 12-15-87

SPUD 12-11-87 3001-35 1/2" Richard

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 4 columns: Plug depth, Formation, Surface pipe, and Notes. Includes entries for 1st through 5th plugs and a note about the mouse hole.

Handwritten log entries:
PUSHER: Pat Wayne
TD: 4823' FORMATION MISS.
SURFACE PIPE: 8 7/8 @ 291'
ANHYDRITE: ELEVATION 2128
STARTING TIME & DATE: 6:00 AM
COMPLETION TIME & DATE: 7:45 AM
1st PLUG @ 1400 FT. W/ 50 SX
2nd PLUG @ 660 FT. W/ 50 SX
3rd PLUG @ 300 FT. W/ 40 SX
4th PLUG @ 40-0 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ H.L.W. will call
Hulliburton T-P Cement - CEMENT COMPANY 6/4 Pat 690 -
TECHNICIAN D.G.

7E 2 1/2 W Crossby

CONSERVATION DIVISION Wichita, Kansas