

TO: " 1052297  
STATE CORPORATION COMMISSION

12-4

API NUMBER 15-097-20,293-0000  
125' W C NW NW SEC. 25, T 27 S, R 18 W

CONSERVATION DIVISION - PLUGGING SECTION 4620 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 4620 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME MILLER WELL # 3

TECHNICIAN'S PLUGGING REPORT

COUNTY KIOWA 139.91

OPERATOR LICENSE # 31929

WELL TOTAL DEPTH 4305 FEET

OPERATOR: T.T. PRODUCTION, INC PRODUCTION CSG: SIZE 3 1/2" @ 4292' WITH 125 SX

NAME AND RR # RR #1 BOX 91 SURFACE CASING: SIZE 8 5/8" @ 290' WITH 300 SX

ADDRESS HAVILAND, KS 67059

ABANDONED OIL WELL  GAS WELL  INPUT WELL  INJ WELL  D/A

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 8:00 AM DAY: 04 MONTH: 12 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM MIKE KELSO

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: PERFS AT 4145-49

1ST PLUG PUMP 1 HULL WITH 15 SX CEMENT DISPLACE TO 4000'.

2ND PLUG AT 1090' WITH 10 GEL AND 50 SX CEMENT.

3RD PLUG AT 320' WITH 50 SX CEMENT.

4TH PLUG AT 30' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART \_\_\_\_\_ NONE \_\_\_\_\_

OPERATIONS COMPLETED: HOUR: 12:00 PM DAY: 04 MONTH: 12 YEAR: 1998

ACTUAL PLUGGING REPORT \_\_\_\_\_

1ST PLUG PUMP 1 HULL WITH 15 SX CEMENT DISPLACE TO 4000'. 12-11-98

2ND PLUG AT 1090' WITH 10 GEL AND 50 SX CEMENT.

3RD PLUG AT 320' WITH 50 SX CEMENT.

4TH PLUG AT 30' WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2020' OF 3 1/2" CASING.  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Richard M. Lacey  
(TECHNICIAN) FORM CP-2/3

RML

DEC 16 1998  
60446