

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-097-20540-0000

NE.SW.NE, Sec. 25, T 27 S, R 18 W 1/4

_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Lease Name Thompson Well # 3

Operator: OIL PRODUCERS OF KS.
Name & Address: Box 8647
Wichita, KS 67208

County K I O W A

Well Total Depth 4813 feet \$156.42

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 7/8 feet 323

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 2 PM Day: 5 Month: OCT Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO BOB BRENNEMAN

(company name) Kelso (phone) _____

were: Plug bottom of 4 1/2" set @ 4812' - PERFS @ 4751-61' -
with 35 sy cmt. to 4700' - USE 60/40 foamix, 2% gel -
3% CC - mix & pump following sequence - 3 sy hulls,
10 sy gel, 50 sy cmt; 10 sy gel, 1 sy hulls, release 8 7/8
plug and finish w/ 100 sy cmt.

orders by P. Luthi

Signed R. Barbutton (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 3 pm Day: 5 Month: OCT Year: 1983

ACTUAL PLUGGING REPORT Plugged as ordered.

Max. pump pressure @ 400#
Shut-in ✓ ✓ 100#
Cementing by Allied.

Remarks: Recovered 3000' of 4 1/2"

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

INVOICED

DATE 10-27-83

INV. NO. 5937-W

RECEIVED STATE CORPORATION COMMISSION

OCT 2 1983
10-12-83
CONSERVATION DIVISION
Wichita, Kansas

Signed R. Barbutton (TECHNICIAN)