

1-041112

10-16

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
WICHITA STATE OFFICE BUILDING
WICHITA, KANSAS 67202

API number: Completed 11/16/72

S/2 SE SEC. 24, 27 S, 18 W
660 feet from S section line
1320 feet from E section line

Operator license# 8061

Lease Thompson well # 1

Operator: Oil Producers, Inc. of Kansas

County Kiowa 156.16

Address: P.O. Box 8647
Wichita, KS 67208

Well total depth 4805 feet
Conductor Pipe:
Surface pipe: 8 5/8" set at 303'

Aband. Oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: D S & W Well Servicing, Inc. License# 6901

Address: P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 8:45 a.m. Day: 16 Month: October Year: 1995

Plugging proposal received from: Kevin Strube

Company: D S & W Well Servicing, Inc. Phone: 316-587-3361

Were: 4 1/2" at 4775' w/100 sx cement, PBSD 4721', Perfs at 4712-16'

1st plug sand back to 4660' and dump 4 sx cement on top.
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,
release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by: Richard Lacey

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 9:30 a.m. Day: 16 Month: October Year: 1995

Actual plugging report:

1st plug sanded back to 4660' and dumped 4 sx cement on top of sand bridge through
dump bailer.

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx
cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx
cement.

Maximum pressure 400 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2336' of 4 1/2"
casing.

I did[X] / did not[] observe the plugging.

Stephen J. Pfeifer
(agent)

INVOICED

DATE 10-27-95

INV. NO. 43874

RECEIVED
STATE CORPORATION COMMISSION
10-8-95
604 (112)
CONSERVATION DIVISION
Wichita, Kansas