

To: 040812 12-2
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-20,282-0000
C SW SW, SEC. 24, T 27 S, R 18 W/EX
660 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061
Operator: Oil Producers Inc. of Kansas
Name & Address: P.O. Box 4
Pratt, KS 67124

Lease Name Thompson Well # 2
County Kiowa
Well Total Depth 4730 153.73 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 326

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 3:15 p.m. Day: 2 Month: 12 Year: 1993

Plugging proposal received from David Brady
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

Work: 4 1/2" at 4721' w/175 sx cement, Perfs at 4142-50', Open hole 4721-30'
1st plug sand back to 4090' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper
plug and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 4:15 p.m. Day: 2 Month: 12 Year: 1993

ACTUAL PLUGGING REPORT 1st plug sanded back to 4090' and dumped 4 sx cement on top of sand
bridge through bailer,
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.
Maximum pressure 300 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2330' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)
INVOICED (10) (XXXXXX) observe this plugging.

DATE DEC 14 1993
INV. NO. 39578

RECEIVED STATE CORPORATION COMMISSION
DEC 09 1993
Signed Stephen J. [Signature] CONSERVATION DIVISION
(TECHNICIAN) WICHITA, KANSAS
FORM CP-2 Rev. 01-