

1041297

3-5

API NUMBER 13-097-20,421-0000

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

CNE SE, SEC. 13, T. 27 S, R. 17 W/4

3-11-98

1980 feet from S section line

TECHNICIAN'S PLUGGING REPORT

RECEIVED  
KANSAS CORP. COMM.

660 feet from E section line

Operator License 131938

Lease Name Clark Well # 1-13

Operator: Indian Oil Co., Inc.

1998 MAR 11 A 11:49

County Kiowa 151.55'

Name & Address P.O. Box 209, 2507 SE 160 Hwy,  
Medicine Lodge, KS 67104

Well Total Depth 4663 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8" feet 445

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SKD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Quality Well Service License Number 31925

Address 249 E. Beth Dr., Sterling, KS 67579

Company to plug at: Hour: 4:00 P.M. Day: 5 Month: 3 Year: 19 98

Plugging proposal received from Richard McIntyre

(company name) Quality Well Service (phone) 316-727-3410

work: 4 1/2" @ 4657' w/ 225 sx. cement, PRTD @ 4663, Perfs. @ 4608'-4611', open hole @ 4657'-4663'

1<sup>st</sup> plug pump down 4 1/2" casing w/ 100# hulls + 25 sx. common cement

2<sup>nd</sup> plug spot 50 sx. cement @ 1025'

3<sup>rd</sup> plug spot 50 sx. cement @ 470'

4<sup>th</sup> plug spot 10 sx. cement @ 40'

Plugging Proposal Received by Scott Albera (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 5:30 P.M. Day: 5 Month: 3 Year: 19 98

ACTUAL PLUGGING REPORT 1<sup>st</sup> plug pumped down 4 1/2" casing w/ 100# hulls @ 25 sx. common cmt. 3<sup>rd</sup> plug  
Spot plugs thru 4 1/2" casing. Top of plug @ 4551'

2<sup>nd</sup> plug lead hole w/ gel + spotted 50 sx cement @ 1025'

3<sup>rd</sup> plug spotted 50 sx. cmt @ 470'

4<sup>th</sup> plug spotted 10 sx. cmt @ 40'

Recovered 2527' of 4 1/2" casing

Remarks: 1<sup>st</sup> plug (bottom plug) used 100# hulls + 25 sx common cmt. 3<sup>rd</sup> plug used 60/40 poz 6 gel by Allied.  
(For additional description is necessary, use BACK of this form.)

INVOICED

I (did / did not) observe this plugging.

DATE MAR 11 1998

Signed Stephen J. P... (TECHNICIAN)

INV. NO. 50218