

1 060535

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-21, 104-0000
C W/2 NW _____, SEC. 21, T 27 S, R 17 W/E

3960 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name McFadden Well # 1-21

Operator: Texas Energies, Inc.
Name &
Address P. O. Box 947
Pratt, KS 67124

County Kiowa 157.63

Well Total Depth 4850 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 487

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A x

Other well as hereinafter indicated _____

Plugging Contractor Wheatstate Oilfield Services, Inc. License Number 5149

Address P. O. Box 329, Pratt, KS 67124

Company to plug at: Hour: 1:00 pm Day: 5 Month: April Year: 19 85

Plugging proposal received from Roland Hogan

(company name) Wheatstate (phone) 316-672-7514

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2130' with 50 sx cement

2nd plug at 510' with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3:00 pm Day: 5 Month: April Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2130' with 50 sx cement, 2nd plug at 510' with 50 sx
cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with

10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate
mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 12 1985

4-12-85

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Dowell

(additional description, if necessary, use BACK of this form.)
Steve Durkan saw all of this operation

observe this plugging.

DATE 4-18-85

INV. NO. 7783

4-5

Signed Paul A. Luthi
(TECHNICIAN)