

1091044  
TO:  
STATE CORPORATION COMMISSION

API NUMBER 15-047-10,126-0001  
SE SE SW SEC. 2, T 24 S, R 17 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM SOUTH SECTION LINE  
WICHITA STATE OFFICE BLDG., 130 S. MARKET 2970 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME MASSEY WELL # 1-2  
TECHNICIAN'S PLUGGING REPORT 4/19 COUNTY EDWARDS 141.15  
OPERATOR LICENSE # 5056 WELL TOTAL DEPTH 4343 FEET

OPERATOR: F.G. HOLL COMPANY, LLC PRODUCTION CSG: SIZE 4 1/2" @ 4342' WITH 150 SX  
NAME AND PO BOX 780167 SURFACE CASING: SIZE 8 5/8" @ 269' WITH 225 SX  
ADDRESS WICHITA, KS 67278-0167

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD WELL  D/A

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR QUALITY WELL SERVICE LICENSE NUMBER 31925

ADDRESS 249 EAST BETH DR. STERLING, KS 67579

COMPANY TO PLUG AT: HOUR: 2:30 PM DAY: 19 MONTH: 04 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM RICHARD MCNTYRE RECEIVED  
STATE CORPORATION COMMISSION

(COMPANY NAME) QUALITY WELL SERVICE (PHONE) 316-727-3410

APR 25 2000

WERE: PERFS AT 4276-4286

1ST PLUG SANDED TO 4200' AND 4 SX CEMENT. FILL HOLE WITH MUD. 2ND PLUG AT 600' WITH CONSERVATION DIVISION  
WICHITA, Kansas

50 SX CEMENT. 3RD PLUG PULL TO 300' SPOT 50 SX CEMENT. 4TH PLUG PULL TO 40' FILL WITH  
10 SX CEMENT. STAYED FULL.

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART  NONE

OPERATIONS COMPLETED: HOUR: 3:30 PM DAY: 19 MONTH: 04 YEAR: 2000

ACTUAL PLUGGING REPORT \_\_\_\_\_

1ST PLUG SANDED TO 4200' AND 4 SX CEMENT. FILL HOLE WITH MUD. 2ND PLUG AT 600' WITH  
50 SX CEMENT. 3RD PLUG PULL TO 300' SPOT 50 SX CEMENT. 4TH PLUG PULL TO 40' FILL WITH  
10 SX CEMENT. STAYED FULL.

INVOICED

DATE 4/26/00

BY 06/6/00

REMARKS: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 600' OF 4 1/2" CASING.  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED \_\_\_\_\_  
(TECHNICIAN) FORM CP-2/3