

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-21337-00-00
Spot: CNENESW Sec/Twnshp/Rge: 13-24S-17W
2310 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: MILLER Well Number: 5-13
County: EDWARDS Total Vertical Depth: 4430 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 6427 EAST KELLOGG
WICHITA, KS 67207

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 309 WITH 225 SX CMT
Production: Size 4.5 feet: 4425 WITH 225 SX CMT *5/43.98*
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 06/21/2001 2:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (316) 278-2026

Proposed Plugging Method: SAND BACK TO 4210' & 4 SX CMT. 1ST PLUG SPOT 50 SX CMT AT 1110'. 2ND PLUG SPOT 50 SX CMT AT 340'. 3RD PLUG SPOT 10 SX CMT AT 0-40'. USE 15 SX GEL FOR SPACER.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/21/2001 4:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 4388'. PERFS AT 4264-4268'. SAND TO 4210' & 4 SX CMT WITH BAILER. PUMP PLUGS THROUGH CASING. 1ST PLUG AT 1110' WITH 13 SX GEL - 50 SX CMT - 2 SX GEL . 2ND PLUG AT 340' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

INVOICED
DATE 6-25-01
INV. NO. 3001061974

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 25 2001
6-25-01
CONSERVATION DIVISION

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2647' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

JUN 22 2001

[Signature]
Form CP-213