

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-047-21381-00-00  
Spot: CW2W2 Sec/Twnshp/Rge: 19-24S-17W  
2490 feet from S Section Line, 4620 feet from E Section Line  
Lease/Unit Name: HOAR Well Number: 1-19  
County: EDWARDS Total Vertical Depth: 4607 feet

Operator License No.: 5056  
Op Name: HOLL, F.G., COMPANY L.L.C.  
Address: 6427 EAST KELLOGG  
WICHITA, KS 67207

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 380 WITH 250 SX CMT  
Production: Size 4.5 feet: 4609 WITH 225 SX CMT <sup>149.73</sup>  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/20/2001 10:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Revd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (316) 278-2026

Proposed Plugging Method: SAND BACK TO 4400' & 4 SX CMT. 1ST PLUG AT 1200' WITH 50 SX CMT. 2ND PLUG AT 410' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT. USE 15 SX GEL FOR SPACER.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 06/20/2001 1:50 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 4583'. PERFS AT 4454-4462'. SAND TO 4400' & 4 SX CMT WITH DUMP BAILER. PUMPED DOWN 4 1/2" CASING WHILE PULLING. 1ST PLUG AT 1200' WITH 15 SX GEL - 50 SX CMT. 2ND PLUG AT 410' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

INVOICED  
DATE 6-25-01  
INV. NO. 2001061974  
RECEIVED  
KANSAS CORPORATION COMMISSION  
JUN 25 2001  
6-25-01  
CONSERVATION DIVISION

Remarks: USED 60/40 POZMIX 6% GEL BY UNITED CEMENTING. RECOVERED 2535' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed Richard M. Lacey  
(TECHNICIAN)

JUN 22 2001

Form 07-2/3