

1052410

TO: STATE CORPORATION COMMISSION

API NUMBER 15-047-21,299-00-00
SW SW NE SEC. 25, T 24 S, R 17 W

CONSERVATION DIVISION - PLUGGING SECTION 2970 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2310 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME STAPLETON A WELL # 1-25

TECHNICIAN'S PLUGGING REPORT 8/2 COUNTY STAFFORD 146.87

OPERATOR LICENSE # 5056 WELL TOTAL DEPTH 4519 FEET

OPERATOR: F.G. HOLL COMPANY, LLC PRODUCTION CSG: SIZE 4 1/2" @ 4518' WITH SX

NAME AND PO BOX 780167 SURFACE CASING: SIZE 8 5/8" @ 302' WITH SX

ADDRESS WICHITA, KS 67278-0167

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR QUALITY WELL SERVICE LICENSE NUMBER 31925

ADDRESS 249 BETH DRIVE, STERLING, KS 67579

COMPANY TO PLUG AT: HOUR: 1:30 PM DAY: 02 MONTH: 08 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM RICHARD MCINTYRE STATE CORPORATION COMMISSION

(COMPANY NAME) QUALITY WELL SERVICE (PHONE) 316-727-3410 AUG - 7 2000

WERE: PERFS AT 4369-4407 CONSERVATION DIVISION Wichita, Kansas

SANDED TO 4303' AND 4 SX CEMENT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING WHILE

PULLING. 1ST PLUG AT 1200' WITH 13 SX GEL - 50 SX CEMENT - 2 SX GEL. 2ND PLUG AT 340'

WITH 50 SX CEMENT. 3RD PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 3:30 PM DAY: 02 MONTH: 08 YEAR: 2000

ACTUAL PLUGGING REPORT

SANDED TO 4303' AND 4 SX CEMENT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING WHILE

PULLING. 1ST PLUG AT 1200' WITH 13 SX GEL - 50 SX CEMENT - 2 SX GEL. 2ND PLUG AT 340'

WITH 50 SX CEMENT. 3RD PLUG AT 40' WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 2343' OF 4 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING

INVOICED

DATE 8/8/00 SIGNED

Richard W. Lacey (TECHNICIAN)

WV. NO. 1060326

FORM CP-2/3

Handwritten initials/signature