

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-20973-00-00
Spot: NESESWNW Sec/Twnshp/Rge: 24-24S-16W
2285 feet from N Section Line, 1015 feet from W Section Line
Lease/Unit Name: BELVA MONTGOMERY Well Number: 3
County: EDWARDS Total Vertical Depth: 4130 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

Conductor Pipe: Size feet: 134.23
Surface Casing: Size 8.625 feet: 430 WITH 250 SX CMT
Production: Size 4.5 feet: 4130 WITH 300 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/30/2001 9:45 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3700' & 4 SX CMT. 1ST PLUG AT 1050' WITH 50 SX CMT. 2ND PLUG AT 460' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT. USE 15 SX GEL FOR SPACER.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/30/2001 11:15 AM KCC Agent: SCOTT ALBERG

Actual Plugging Report:
PBTD 4094'. PERFS AT 3784-3800'. SAND TO 3700' & 4 SX CMT ON TOP. 1ST PLUG PUMP 15 SX GEL & 50 SX CMT AT 1030'. 2ND PLUG PULL TO 450' & PUMP 50 SX CMT. 3RD PLUG PUMP 10 SX CMT AT 0-40'. GOOD CIRCULATION THROUGHOUT JOB.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLED. RECOVERED 3700' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
DEC 06 2001
KCC WICHITA
12-6-01

Signed [Signature]
(TECHNICIAN)

INVOICED DEC 03 2001
DATE 12-7-01
INV. NO. 2002061036

FORM 113