

1052389

-0001

TO: STATE CORPORATION COMMISSION

API NUMBER 15-047-20,951-A
75'S 75'E NW NW SE SEC. 15, T 24 S, R 16 W

CONSERVATION DIVISION - PLUGGING SECTION 2235 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2235 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME SCHNACK-PYLE WELL # 2-15

TECHNICIAN'S PLUGGING REPORT

COUNTY EDWARDS 144.95

OPERATOR LICENSE # 5056 4/24

WELL TOTAL DEPTH 4460 FEET

OPERATOR: F.G. HOLL COMPANY, LLC

PRODUCTION CSG: SIZE 5 1/2" @ 4460' WITH 200 SX

NAME AND PO BOX 780167

SURFACE CASING: SIZE 8 5/8" @ 395' WITH 350 SX

ADDRESS WICHITA, KS 67278-0167

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ACID SERVICES LICENSE NUMBER NA

ADDRESS PO BOX 8613 PRATT, KS 67124-8613

COMPANY TO PLUG AT: HOUR: 4:00 PM DAY: 24 MONTH: 04 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM ROB LONG

(COMPANY NAME) ACID SERVICES (PHONE) 316-672-1201

WERE: PERFS AT 4326-4336, 4279-4299 WELL WAS PERFORATED AT 500' & 1000' & SQUEEZED WITH CEMENT BACK TO SURFACE IN 1986.

PUMP 300# HULLS - 25 SX CEMENT - 25 SX GEL - 65 SX CEMENT. MAXIMUM PRESSURE 1000 PSI.

SHUT IN 500 PSI.

PLUGGING PROPOSAL RECEIVED BY STEVE DURRANT

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 4:58 PM DAY: 24 MONTH: 04 YEAR: 2000

ACTUAL PLUGGING REPORT

PUMPED 300# HULLS - 25 SX CEMENT - 25 SX GEL - 65 SX CEMENT. MAXIMUM PRESSURE 1000 PSI.

SHUT IN 500 PSI.

RECEIVED STATE CORPORATION COMMISSION

REMARKS: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED DATE 5/9/00 SIGNED Richard W. Lacey (TECHNICIAN)

MAY 11 2000 CONSERVATION DIVISION Wichita, Kansas

INV. NO. 61694

FORM CP-2/3

(Handwritten signature/initials)