

TO: *R*
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-20982-00-00
Spot: CSENWNW .Sec/Twnshp/Rge: 24-24S-16W
990 feet from N Section Line, 990 feet from W Section Line
Lease/Unit Name: BELVA MONTGOMERY Well Number: 4
County: EDWARDS Total Vertical Depth: 4130 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 410 WITH 250 SX CMT
Production: Size 4.5 feet: 4130 WITH 250 SX CMT
Liner: Size _____ feet:
8/34.23

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/28/2001 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Revd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND BACK TO 3750' & 4 SX CMT ON TOP. 1ST PLUG AT 1050' WITH 50 SX CMT. 2ND PLUG AT 440' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT. USE 15 SX GEL FOR SPACER.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/28/2001 12:50 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 4092'. PERFS AT 3798-3804'. TOC 2059-2070'. SAND TO 3740' & 4 SX CMT WITH DUMP BAILER. PUMPED PLUGS THROUGH CASING. 1ST PLUG AT 1050' WITH 13 SX GEL - 50 SX CMT - 2 SX GEL. 2ND PLUG AT 440' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2300' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Richard M. Lacey

(TECHNICIAN)

NOV 30 2001

[Signature]

Form CP-2/3

RECEIVED
DEC 03 2001
KCC WICHITA

INVOICED

DATE 12-4-01

INV. NO. 2002061024