

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-20942-00-00
Spot: CNWNWNW Sec/Twnshp/Rge: 24-24S-16W
330 feet from N Section Line, 330 feet from W Section Line
Lease/Unit Name: BELVA MONTGOMERY Well Number: 2
County: EDWARDS Total Vertical Depth: 4120 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

Conductor Pipe: Size feet: 8 1/33.98
Surface Casing: Size 8.625 feet: 394 WITH 250 SX CMT
Production: Size 4.5 feet: 4120 WITH 250 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/03/2001 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3730' & 4 SX CMT. 1ST PLUG AT 1050' WITH 15 SX GEL - 50 SX CMT. 2ND PLUG AT 440' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/03/2001 3:35 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 4083'. PERFS AT 3780-3802, 3818-22, 3920-30, 3975-82'. SANDED TO 3730' & 4 SX CMT WITH DUMP BAILER. PUMP PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 1009' WITH 15 SX GEL - 50 SX CMT. 2ND PLUG AT 440' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2308' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Richard M. Lacey

(TECHNICIAN)



RECEIVED

DEC 06 2001

KCC WICHITA

INVOICED

DATE

12-7-01

INV. NO.

2002061036

DEC 04 2001

MD