

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-047-21379-00-00  
Spot: CSWNWSW Sec/Twnshp/Rge: 5-24S-17W  
1650 feet from S Section Line, 4950 feet from E Section Line  
Lease/Unit Name: DELORES Well Number: 1-5  
County: EDWARDS Total Vertical Depth: 4490 feet

Operator License No.: 5056  
Op Name: HOLL, F.G., COMPANY L.L.C.  
Address: 6427 EAST KELLOGG  
WICHITA, KS 67207

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 270 WITH 225 SX CMT  
Production: Size 4.5 feet: 4489 WITH 225 SX CMT  
Liner: Size \_\_\_\_\_ feet: 8145.93

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/22/2001 2:45 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: TERRY BAIRD Company: F.G. HOLL Phone: (316) 684-8481

Proposed Plugging Method: SAND TO 4289' & 4 SX CMT. 1ST PLUG AT 1200' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 06/22/2001 3:45 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:  
PBTD 4440'. PERFS AT 4342-44' & 4354-58'. SANDED BACK TO 4290' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. LOAD HOLE WITH GEL. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 1200' WITH 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

**INVOICED**  
DATE 6-27-01  
INV NO. 2001062010

RECEIVED  
KANSAS CORPORATION COMMISSION  
6-27-01  
JUN 27 2001

Remarks: USED 604/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2637' OF 4 1/2" CASING.  
Plugged through: CSG

District: 01 Signed Stephen J. Pfeifer (TECHNICIAN)  
JUN 26 2001 Form CH-23