

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-035-23628-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date. 5/02

WELL OPERATOR Gen-Dor Oil Co. KCC LICENSE # 9576
(owner/company name) (operator's)
ADDRESS Box 254 CITY Burden,
STATE Kansas ZIP CODE 67019 CONTACT PHONE # (316) 438-2885
LEASE Whiteman SWD WELL# 1 SEC. 10 T. 30 R. 7 (East/West)
N/2 - S/2 - SE SPOT LOCATION/0000 COUNTY Cowley

990 FEET (in exact footage) FROM (S)N (circle one) LINE OF SECTION (NOT Lease Line)
1320 FEET (in exact footage) FROM (E)W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# D-25,404

CONDUCTOR CASING SIZE 5 1/2" SET AT _____ CEMENTED WITH _____ SACKS
SURFACE CASING SIZE 8 5/8" SET AT 350 CEMENTED WITH _____ SACKS
PRODUCTION CASING SIZE 5 1/2" SET AT 3440 CEMENTED WITH Bottom: 6 sacks
Top: 120 sacks SACKS
400 lb gel 42

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 2425 (2372 to 2384)

ELEVATION 1455 T.D. 3440 PBDT 2425 ANHYDRITE DEPTH _____
(G.L./K.B.) plug (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING sand back to 2,220 ft and dump 6 sacks of cement.

top: rig up to tubing, set at 350'. Pump cement back to surface. Pull tubing and fill hole with cement.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED?

If not explain why? Log filed with KCC

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

RECEIVED
KANSAS CORPORATION COMMISSION

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Ronnie Whiteman (Gen-Dor Oil Co.) PHONE# (316) 438-2885 MAY 7 2001

ADDRESS Box 254 City/State Burden, KS 67019

PLUGGING CONTRACTOR Bottom: B.P.C. Well Plugging KCC LICENSE # _____

ADDRESS PO Box 134 Augusta, KS 67010 (company name) PHONE # (316) 438-2856 (contractor's)

Top plug: Blue Star Acid Service PO Box 103 Eugene, KS 67045 PH: 620-583-7664
PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 4-23-01 6 PM

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 5-4-01 AUTHORIZED OPERATOR/AGENT: Merle L. King
(signature)

CONSERVATION DIVISION

BLUE STAR ACID SERVICE, INC.

PO Box 103
Eureka, Kansas 67045

Cementing Ticket
and Invoice Number

No 2714

Date	Customer Order No.	Secl.	Twp.	Range	Truck Called Out	On Location	Job Began	Job Completed	
4-23-01						8:00 Am	8:30 Am	6:00 pm	
Owner				Contractor			Charge To		
Gen Dor Oil				Co, Tools			Gen-Dor Oil Company		
Mailing Address				City			State		
P.O. Box 254				Burden			Kansas 67019-0254		
Well No. & Form		Place		County		State			
Whiteman S.W.O. #1				Cowley		Kansas			
Depth of Well		Depth of Job	Casing	(New) (Used)	Size	Size of Hole Amt. and Kind of Cement	Cement Left in casing by	Request Necessity	
350-					5 7/8	7 7/8" 120 SKS			
Kind of Job				Drillpipe		(Rotary)		Truck No.	
Pumping Job / P.T.A.				Tubing		(Cable)		Unit #2	

Price Reference No. _____
 Price of Job 425.00
 Second Stage 300.00
 Mileage 35 78.75
 Other Charges _____
 Total Charges 803.75

Remarks Rig up to 2 7/8" with Power-Swivel, circulate on well while drilling out cement, we had good cement to 200', we ran Tubing with a 7 7/8" Bit down to 350' and circulated hole clean Round Trip Tubing, Took Bit off, To be ready to cement

Rig up to Tubing set at 350', Mixed cement with 18 Bbls water, we had good cement returns to surface, shut down, Pull Tubing out of well, Fill Hole back up with cement, 20 Bbls mixing water. Hole stayed full. Job complete with 20 Bbls mixing water used wash up and tear down.

Cementor Brad Butler
 Helper Steve Jason District Eureka State Kansas

"Thank you"
 Called by Ronnie Whiteman Agent of contractor or operator

Sales Ticket for Materials Only

Quantity Sacks	BRAND AND TYPE	PRICE	TOTAL
120	SKS 60/40 Pozmix cement	6.50	780.00
400	lbs Geh 42	9.50	38.00
Plugs	120 SKS Handling & Dumping	.50	60.00
	5.2 Tons Mileage 35	.80	145.60
	Sub Total		1827.35
	Delivered by Truck No. Unit #4	Discount	
	Delivered from Eureka	Sales Tax	5.9%
	Signature of operator Brad Butler	Total	1935.16

RECEIVED
 KANSAS CORPORATION COMMISSION
 MAY 7 2001
 CONSERVATION DIVISION

Robert L. Braden
 316-775-7132
 316-644-0145

B.P.C. Well Plugging
 P.O.Box 134
 Augusta, Kansas 67010

Jim Braden
 316-438-2856
 316-648-2643

GEN-DOR OIL COMPANY
 P.O. BOX 254
 BURDEN, KANSAS 67019

LEASE WHITEMAN	WELL NO. #1 SWD	INVOICE NO. 97-125	DATE 11-4-97
DATE	DESCRIPTION	AMOUNT	
10-30-97	MOVED RIG TO LOCATION. RIGGED UP TO PLUG BOTTOM. SANDED BACK TO 2,220 FEET AND DUMPED 6 SACKS OF CEMENT.		
11-3-97	RIGGED UP JACKS AND PULLED SLIPPS. SHOT PIPE OFF AT 950 FEET. LAID DOWN 5½" CASING.		
	RIG UP AND PLUG WELL.		\$1,000.00
	PULLED 950 FEET OF CASING @.50 ¢ PER FOOT		475.00
	TOTAL		\$1,475.00

RECEIVED
 KANSAS CORPORATION COMMISSION
 MAY 7 2001
 CONSERVATION DIVISION

Please Pay From This Invoice
 Statement will be sent on request.
 TERMS: NET 10 DAYS From Date of Invoice. A Service Charge of 1 1/2% Will Be Added to Past Due Accounts.
 (Effective Rate 18% Per Annum)



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

March 7, 2001

Mr. Merle Krug
Mr. Ronnie Whiteman
Gen-Dor Oil Co.
PO Box 254
Burden, Kansas 67019

Re: Meeting concerning Whiteman #1 (D-25,404) SE/4 10-30-7E, Cowley County

Gentlemen: Thank you for meeting with Butch and I today. I am writing today, as I said I would during the meeting, to formalize what we agreed upon. Within 45 days, by April 23, Gen-Dor will move it's company rig over the Whiteman #1 drill it out to 350 feet, run back in with tubing and circulate cement from 350 to surface. One week before moving in, you will notify Butch and he will witness the drilling and plugging. Please call me if you have any questions, 316 337-6231.

Sincerely,

Doug Louis
District Supervisor

cc: Butch Hoberecht

*Whiteman #1 SWD Completed
AND Plugged to specifications on
(Michael R. Wilson on location)
4-23-01*

*Thanks
Gen-Dor Oil Co.*

KANSAS CORPORATION COMMISSION

MAY 7 2001

CONSERVATION DIVISION



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Gen-Dor Oil Co.
PO Box 254
Burden, KS 67019

May 11, 2001

WHITEMAN #1
API 15-035-23628-00-00
990 S 1320 E
CN2S2SE 10-30S-7E
COWLEY COUNTY

Dear Ronnie Whiteman:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script that reads "David P. Williams".

David P. Williams
Production Supervisor

District: #2
130 S. Market, Room 2125
Wichita, KS 67202-3208
(316) 337-6231