

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FEB 20 2001

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-047-21337-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR F. G. Holl Company, L.L.C. KCC LICENSE # 5056
(owner/company name) (operator's)

ADDRESS 6427 E. Kellogg P.O. Box 780167 CITY Wichita

STATE Kansas ZIP CODE 67278-0167 CONTACT PHONE # (316) 684-8481

LEASE MILLER WELL# 5-13 SEC. 13 T. 24S R. 17W (East/West)

NE . NE . SW . SPOT LOCATION/QOOO COUNTY Edwards

2310 FEET (in exact footage) FROM (S)/N (circle one) LINE OF SECTION (NOT Lease Line)

2970 FEET (in exact footage) FROM (E)/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL ___ GAS WELL X D&A ___ SWD/ENHR WELL ___ DOCKET# _____

CONDUCTOR CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 309' CEMENTED WITH 225 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 4425' CEMENTED WITH 225 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4264 - 4268* Cherokee Sand

ELEVATION 2095 GL T.D. 4430' PBDT 4388' ANHYDRITE DEPTH 1106
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD ___ POOR ___ CASING LEAK ___ JUNK IN HOLE ___

PROPOSED METHOD OF PLUGGING Heavy Mud, Hulls, Cement and plug according to KCC regulations.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Rob Long PHONE# (316) 793-0915(Cell)/ 995-3171(Office)

ADDRESS P.O. BOX 158 City/State Belpre, Kansas 67519

PLUGGING CONTRACTOR Quality Well Service Inc. KCC LICENSE # 31925
(company name) (contractor's)

ADDRESS 249 Beth Drive Sterling, KS 67579 PHONE # (316) 278-2476

PROPOSED DATE AND HOUR OF PLUGGING (If known?) Not known

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 02-14-2001 AUTHORIZED OPERATOR/AGENT: _____

(signature)
Franklin R. Greenbaum

RECEIVED
STATE CORPORATION COMMISSION

2-21-01
FEB 21 2001

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG -----Miller #5-13
located NE NE SW, Section 13-T24S-R17W, Edwards
County, Kansas

OWNER: F. G. Holl Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: May 5, 1989

COMPLETED: May 15, 1989

LOG

0 - 80'	surface oil & sand
80 - 312'	redbed & shale
312 - 1105'	shale
1105 - 1360'	Anhydrite
1360 - 4430'	lime & shale

CASING RECORD

Ran 7 joints 8 5/8" (24#) new casing.
297.14' pipe set at 309' KB. Cemented
with 225 sacks 40/60 Pozmix W/ 2% Gel
& 3% cc. Plug down at 4:30 PM 5-8-89
Good Returns by BJ Titan

Ran 122 joints used 4 1/2" 10.5# casing.
4417.13' pipe set at 4425' KB. Cemented
with 100 sacks lite cement, followed
with 125 sacks 50/50 Pozmix with regular
F. G. Holl additives. Plug down at 2:00 AM
5-15-89 by BJ Titan

Deviation surveys 3/4° at 4305'



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Holl, F.G., Company L.L.C.
6427 East Kellogg
Wichita, KS 67207

March 12, 2001

MILLER #5-13
API 15-047-21337-00-00
2310 S 2970 E
CNENESW 13-24S-17W
EDWARDS COUNTY

Dear Rob Long:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script that reads "David P. Williams".

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-8888