

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FEB 20 2001

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-047-21,381 - 00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date. *6/01*

WELL OPERATOR F. G. Holl Company, L.L.C. KCC LICENSE # 5056
(owner/company name) (operator's)
ADDRESS 6427 E. Kellogg P.O. Box 780167 CITY Wichita
STATE Kansas ZIP CODE 67278-0167 CONTACT PHONE # (316) 684-8481

LEASE HOAR WELL# 1-19 SEC. 19 T. 24S R. 17 (East/West)
C 150' S of SPOT LOCATION/0000 COUNTY Edwards
W/2 - W/2

2490' FEET (in exact footage) FROM (S)/N (circle one) LINE OF SECTION (NOT Lease Line)
4620' FEET (in exact footage) FROM (E)/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 380' CEMENTED WITH 250 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 4609' CEMENTED WITH 225 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4454 - 4462' Mississippi

ELEVATION 2131 GL T.D. 4607' PBDT 4583' ANHYDRITE DEPTH 1174
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING _____

Heavy Mud, Halls, Cement and plug according to KCC regulations.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Rob Long PHONE# (316) 793-0915 (Cell)/(316) 995-3171

ADDRESS P.O. BOX 158 City/State Belpre, Kansas 67519

PLUGGING CONTRACTOR Quality Well Service Inc. KCC LICENSE # 31925
(company name) (contractor's)

ADDRESS 249 Beth Drive Sterling, KS. 67579 PHONE # (316) 278-2476

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Not known

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 2-14-2001 AUTHORIZED OPERATOR/AGENT: _____

[Signature]
(signature) RECEIVED
Franklin RAT Greenbaum COMMISSION

FEB 21 2001

CONSERVATION DIVISION

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

Sample Log ----- Hoar # 1-19
located 150' S of C-W/2, W/2, Section 19, T 24 S R 17 W, Edwards County, Kansas

OWNER: F.G.Holl Company
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: June 23, 1991.
COMPLETED: June 30, 1991

TOTAL DEPTH: 4610' Driller T.D.
4607' Log T.D.

LOG

0 - 155	Surface Soil & Sand
155 - 381	Redbed & Shale
381 - 1179	Shale
1179 - 1195	Anhydrite
1195 - 4610	Lime & Shale

Casing Record

Spud at 12:30 p.m. June 23, 1991.
Drilled 382' of 12 1/4" hole, Ran
9 joints of 8 5/8" 23 # new casing
367.83' of pipe. Set at 380' K.B.
cemented with 250 sacks of 60 X 40
pozmix, with 2% gel. and 3% CC. Plug
down at 7:00 p.m. 6-23-91 By B.J. Titan.
Good returns to surface.

Ran 112 joints of new & used 4 1/2"
10.5# casing. 4597.45' of pipe (294.37'
used) Set at 4609' K.B. cemented with
20 BBL. of saltflush and 500 gallons of
superflush ahead of 100 sacks of lite
cement followed with 125 sacks of F.G.Holl
mix. Plug down at 3:30 a.m. 6-30-91 by
B.J.Titan, centralizers on joints
1-4-7 and 18. Shoe joint is 12.00' long.
15 sacks cement in rat hole.

Deviation Survey

3/4° at 4472'



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Holl, F.G., Company L.L.C.
6427 East Kellogg
Wichita, KS 67207

March 12, 2001

HOAR #1-19
API 15-047-21381-00-00
2490 S 4620 E
W2W2 19-24S-17W
EDWARDS COUNTY

Dear Rob Long:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-8888