

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

JUL 13 2000
7-13-00
CONSERVATION DIVISION
Wichita, Kansas
FORM CP-1 (5/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-047-21,299 - 00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR F. G. Holl Company, L.L.C. KCC LICENSE # 5056
(owner/company name) (operator's)

ADDRESS 6427 E. Kellogg P.O. Box 780167 CITY Wichita

STATE Kansas ZIP CODE 67278-0167 CONTACT PHONE # (316) 684-8481

LEASE Stapleton "A" WELL# 1-25 SEC. 25 T. 24S R. 17W (~~East~~ West)

SW . SW . NE . SPOT LOCATION/QOOD COUNTY Edwards

2970' FEET (in exact footage) FROM (S/N) (circle one) LINE OF SECTION (NOT Lease Line)

2310' FEET (in exact footage) FROM (E/W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 302' CEMENTED WITH 225 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 4518' CEMENTED WITH 225 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4369-4407'

ELEVATION 2106/2115 T.D. 4520' PBDT 4486' ANHYDRITE DEPTH 1122'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Will plug with Heavy mud, Hulls and plug as instructed by KCC.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Rob long

PHONE# . , (316) 793-0915

ADDRESS P.O. Box 158 City/State Belpre, Kansa 67519

PLUGGING CONTRACTOR Quality Well Service, Inc. KCC LICENSE # 31925

ADDRESS 249 Beth Drive Sterling, KS. 67579 (company name) (contractor's)
PHONE # (X316) 278-2476

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Unknown

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 07/12/2000 AUTHORIZED OPERATOR/AGENT: W. Bryce Bidleman
(signature)

W. Bryce Bidleman

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

RECEIVED
STATE CORPORATION COMMISSION

JUL 13 2000

CONSERVATION DIVISION
Wichita, Kansas

WELL LOG -----STAPLETON A 1-25

Located SW SW NE, Section 25-T24S-R17W, Edwards County, Ks.

OWNER: F. G. HOLL COMPANY

ROTARY DRILLING CONTRACTOR: STERLING DRILLING COMPANY

COMMENCED: 11-19-87

COMPLETED: 11-25-87

ROTARY TOTAL DEPTH: 4520'

LOG

0 - 90	Surface soil & sand
90 - 223	Sand
223 - 1119	Shale
1119 - 1135	Anhydrite
1135 - 2200	Lime & Shale
2200 - 3105	Lime & Shale
3105 - 3820	Lime & Shale
3820 - 4368	Lime & Shale
4368 - 4495	Lime & Shale
4495 - 4520	Lime & Shale

CASING RECORD

Ran 7 joints 8 5/8" 23# new casing.
290.29' set at 302' KB. Cemented with
225 sacks 60/40 Pozmix. Plug down at
6:00 PM 11-19-87 Good Returns to
surface by Halliburton Services

DEVIATION

2120'	1°
4376'	1 3/4°

Ran 110 joints new & used 4 1/2" 10.5#
casing. 4521.51' pipe set at 4518'
KB. Cemented with 100 sacks Lite
cement followed with 125 sacks 50-50
Pozmix with regular F. G. Holl additives.
Plug down at 9:15 PM 11-25-87 by
Halliburton Services.



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Holl, F.G., Company L.L.C.
6427 East Kellogg
Wichita, KS 67207

July 14, 2000

STAPLETON A #1-25
API 15-047-21299-00-00
2970 S 2310 E
SW SW NE 25-24S-17W
EDWARDS COUNTY

Dear Rob Long:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-8888