

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION

FEB 11 2000  
FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

CONSERVATION DIVISION  
Wichita, Kansas

API # 15-047-20,951-A<sup>0001</sup> (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR F. G. Holl Company, L.L.C. KCC LICENSE # 5056  
(owner/company name) (operator's)

ADDRESS 6427 E. Kellogg P.O.Box 780167 CITY Wichita

STATE Kansas ZIP CODE 67278-0167 CONTACT PHONE # (315) 684-8481

LEASE SCHNACK-PYLE WELL# 2-15 SEC. 15 T. 24S R. 16 ~~East~~ West

75' S and 75' E of  
NW - NW - SE SPOT LOCATION/QQQQ COUNTY Edwards

2235 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

2235 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE None SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 395' CEMENTED WITH 350 SACKS

PRODUCTION CASING SIZE 5 1/2" SET AT 4460' CEMENTED WITH 200 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4326-4336', 4279-4299', 1100', and 500'.

ELEVATION 2075' KB T.D. 4460' P.B.T.D. 4390' ANHYDRITE DEPTH 1083'  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING As per KCC rules and regs. Well was originally plugged by Sun Exploration in 1986 and production casing was not pulled. Perfs were placed at 500' and 1100' feet, and cement was circulated through to the surface. No casing can be pulled.  
(If additional space is needed attach separate page)  See Plugging Report.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? Yes

If not explain why? F. G. Holl is the third operator of this well and did not receive a copy of the Well Log.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:  
Rob Long PHONE# (316) 995-3171 Field Office  
793-0915 Cell Phone

ADDRESS P.O. Box 158 City/State Belpre, Kansas 67519

PLUGGING CONTRACTOR Quality Well Service, Inc. KCC LICENSE # 31925  
(company name) (contractor's)

ADDRESS 249 Beth Drive Sterling, Kansas 67579 PHONE # (316) 278-2476

PROPOSED DATE AND HOUR OF PLUGGING (if known?) Not known.

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 2-10-00 AUTHORIZED OPERATOR/AGENT: W. Bruce Bidleman  
(signature)

40/60  
Poz Cement A  
6% gel

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE NAME Schnack-Pyle  
WELL NUMBER 2  
SPOT LOCATION NW/4 SE/4  
SEC. 15 TWP 24S RGE. 16 (X) or (W)  
COUNTY Edwards  
Date Well Completed 12/08/81  
Plugging Commenced 11/11/86  
Plugging Completed 11/14/86

LEASE OPERATOR Sun Exploration and Production Company

ADDRESS 525 Central Park Drive

PHONE # (405) 556-9975 OPERATORS LICENSE NO. 6169

Character of Well gas  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACC-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing formation Miss Chat Depth to top 4240 bottom 4377 T.D. 4460'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippian	Oil & Gas	4279'	4336'	8 5/8"	395'	
				5 1/2"	4460'	

CONSERVATION DIVISION  
Wichita, Kansas

FEB 11 2000

RECEIVED  
STATE CORPORATION COMMISSION

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Kill well with 9 ppg, 36 vis mud, 60 bbls dn csg, and 40 bbls dn tbg. Set CIBP @ 4045', spot 2 sx cmt on CIBP using dump bailer. Fill csg with 9 ppg, 36 vis mud and test to 300#. Perf 4 holes @ 1100 ft. Pump 75 sx cmt out perfs. Perf 4 holes at 500'. Circ csg. with 130 sx cmt -- cmt to surface inside and outside 5 1/2" Cut off csgs. 6' below GI, weld cap on, clean up loc.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Well Services License No. \_\_\_\_\_

Address Box 579, Great Bend, Kansas 67530

STATE CORPORATION COMMISSION

STATE OF Oklahoma COUNTY OF Oklahoma, ss. DEC 24 1986

Susan Carlisle (employee of operator) or CONSERVATION DIVISION  
(operator) of above-described well, being first duly sworn on oath, says: That Wichita, Kansas



## *Kansas Corporation Commission*

*Bill Graves, Governor   John Wine, Chair   Cynthia L. Claus, Commissioner   Brian J. Moline, Commissioner*

### **NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Holl, F.G., Company L.L.C.  
6427 East Kellogg  
Wichita, KS 67207

February 14, 2000

SCHNACK PYLE 2 #OWW  
API 15-047-20951-00-01  
2235 S 2235 E  
NW NW SE 15-24S-16W  
EDWARDS COUNTY

Dear Rob Long:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely,

A handwritten signature in dark ink, appearing to read "David P. Williams".

David P. Williams  
Production Supervisor

District: #1  
304 W. McArtor  
Dodge City, KS 67801  
(316) 225-8888