

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FEB 20 2001

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-047-21,379-06-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date. 4/01

WELL OPERATOR F. G. Holl Company, L.L.C. KCC LICENSE # 5056
(owner/company name) (operator's)
ADDRESS 6427 E. Kellogg P.O. Box 780167 CITY Wichita
STATE Kansas ZIP CODE 67278-0167 CONTACT PHONE # (316) 684-8481
LEASE DELORES WELL# 1-5 SEC. 5 T. 24S R. 17 (East/West)
C - SW - NW - SW SPOT LOCATION/QQQQ COUNTY Edwards

1650' FEET (in exact footage) FROM (S)N (circle one) LINE OF SECTION (NOT Lease Line)
4950' FEET (in exact footage) FROM (E)W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS
SURFACE CASING SIZE 8 5/8" SET AT 270' CEMENTED WITH 225 SACKS
PRODUCTION CASING SIZE 4 1/2" SET AT 4489' CEMENTED WITH 225 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4342 - 4344, Cherokee & 4354-4358' Mississippian
ELEVATION 2115 GL T.D. 4490' PBDT 4440' ANHYDRITE DEPTH _____ Chert
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Heavy Mud, Hulls, Cement and plug according to KCC regulations.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Rob Long PHONE# () (316) 793-0915(C)/(316) 995-3171
Office

ADDRESS P.O. BOX 158 City/State Belpre, KS. 67519

PLUGGING CONTRACTOR Quality Well Service Inc. KCC LICENSE # 31925 8/01

ADDRESS 249 Beth Drive, Sterling, Kansas, 67579 (company name) (contractor's)
PHONE # (316) 278-2476

PROPOSED DATE AND HOUR OF PLUGGING (If known?) Not known

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 2-14-2001 AUTHORIZED OPERATOR/AGENT: Franklin R. Greenbaum

(signature) RECEIVED

Franklin R. Greenbaum
KANSAS CORPORATION COMMISSION

2-21-01 FEB 21 2001

CONSERVATION DIVISION

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

SAMPLE LOG -----Delores # 1-5

located SW-NW-SW Section 5-T24S-R17W
Edwards County, Kansas

OWNER: F.G.Holl Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: June 7, 1991

COMPLETED: June 14, 1991

TOTAL DEPTH: 4490' DTD
4488' LTD

- LOG -

0'-240' Surface soil & sand
240'-275' Shale
275'-1186' Shale
1186'-1206' Anhydrite
1206'-4490' Lime & Shale

CASING RECORD

Spud at 7:30 a.m. 6-7-91. Drilled 275' of 12 1/4" hole. Ran 6 joints of 8 5/8" 23# new casing cemented with 225 sx. of 60 x 40 pozmix with 2 % Gel and 3 % C.C.. Plug down at 11:30 a.m. 6-7-91 by B.J.Titan.-Good returns to surface.

Ran 128 joints of 4 1/2" 10.5# used casing. 4478.02' of pipe set at 4489' K.B. cemented with 20 BBL of salt flush, and 500 gal. of superflush ahead of 100 sx. of lite cement, and 125 sx. of F.G.Holl mix, Plug down at 7:30 a.m. 6-14-91 by B.J. Titan. 15 sx. in the rathole, shoe joint was 20.23' long, centralizers on joints 1-6-14 and 30.

DEVIATION SURVEYS

4366' - 3/4°



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Holl, F.G., Company L.L.C.
6427 East Kellogg
Wichita, KS 67207

March 12, 2001

DELORES #1-5
API 15-047-21379-00-00
1650 S 4950 E
SWNWSW 5-24S-17W
EDWARDS COUNTY

Dear Rob Long:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-8888