

1052412

TO: STATE CORPORATION COMMISSION

API NUMBER 15-047-20,347 - 00 - 00
SW NE NE NE SEC. 6, T 24 S, R 17 W

CONSERVATION DIVISION - PLUGGING SECTION 440 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 440 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME CROSS WELL # 1-6

TECHNICIAN'S PLUGGING REPORT COUNTY EDWARDS 143.98

OPERATOR LICENSE # 5056 7/31 WELL TOTAL DEPTH 4430 FEET

OPERATOR: F.G. HOLL COMPANY, LLC PRODUCTION CSG: SIZE 4 1/2" @ 4467' WITH 150 SX

NAME AND PO BOX 780167 SURFACE CASING: SIZE 8 5/8" @ 254' WITH 225 SX

ADDRESS WICHITA, KS 67278-0167

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR QUALITY WELL SERVICE LICENSE NUMBER 31925

ADDRESS 249 BETH DRIVE, STERLING, KS 67579

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 31 MONTH: 07 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM RICHARD MCINTYRE

(COMPANY NAME) QUALITY WELL SERVICE (PHONE) 316-727-3410

WERE: PERFS AT 4368-4404

PUMPED 200# HULLS - 30 SX COMMON CEMENT DOWN 4 1/2". TOP OF PLUG 2500'. SPOTTED PLUGS

THROUGH CASING WHILE PULLING. 1ST PLUG AT 1200' WITH 12 SX GEL - 50 SX CEMENT - 3 SX GEL.

2ND PLUG AT 280' WITH 50 SX CEMENT. 3RD PLUG AT 40' WITH 10 SX CEMENT.

RECEIVED
STATE CORPORATION COMMISSION

AUG - 7 2000

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART CONSERVATION DIVISION NONE
Wichita, Kansas

OPERATIONS COMPLETED: HOUR: 10:47 AM DAY: 31 MONTH: 07 YEAR: 2000

ACTUAL PLUGGING REPORT

PUMPED 200# HULLS - 30 SX COMMON CEMENT DOWN 4 1/2". TOP OF PLUG 2500'. SPOTTED PLUGS

THROUGH CASING WHILE PULLING. 1ST PLUG AT 1200' WITH 12 SX GEL - 50 SX CEMENT - 3 SX GEL.

2ND PLUG AT 280' WITH 50 SX CEMENT. 3RD PLUG AT 40' WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 2231' OF 4 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED SIGNED Richard W. Lacey (TECHNICIAN) FORM CP-2/3
DATE 8/8/00
WV. NO. 1060326