

APR 24 2000

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

CONSERVATION DIVISION
WICHITA, KS

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-047-20,352 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR F. G. Holl Company, L.L.C. KCC LICENSE # 5056
(owner/company name) (operator's)

ADDRESS 6427 E. Kellogg P.O. Box 780167 CITY Wichita

STATE Kansas ZIP CODE 67278-0167 CONTACT PHONE # (316) 684-8481

LEASE Miller WELL# 1-13 SEC. 13 T. 24 R. 17W (East/West)

SE. SE. SW SPOT LOCATION/QQQQ COUNTY Edwards

330' FEET (in exact footage) FROM S (circle one) LINE OF SECTION (NOT Lease Line)

2970' FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8 5/8" SET AT 251.6 KB CEMENTED WITH 225 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 4449'KB CEMENTED WITH 150 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4348-4350', 4348-4350'

ELEVATION 2095/2104 T.D. 4450" P.B.T.D. 4421' ANHYDRITE DEPTH 1105-1124'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Heavy mud, Hulls, Cement and Halliburton plug.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Rob long

PHONE# (316) 793-0915

ADDRESS P.O. Box 158 City/State Balpre, Kansa 67519

PLUGGING CONTRACTOR Quality Well Service, Inc. KCC LICENSE # 31925

ADDRESS 249 Beth Drive Sterling, KS. 67579 (company name) (contractor's)
PHONE # (X316) 278-2476

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Unknown

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 04/20/2000

AUTHORIZED OPERATOR/AGENT:

(signature)

Frank Greenbaum

APR 24 2000

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

CONSERVATION DIVISION
WICHITA, KS

WELL LOG ----- HILLER #1-13

Located: SE SE SW, Section 13-24S-17W, Edwards County,
Kansas

OWNER: F. G. Holl, et al
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: March 27, 1978
COMPLETED: April 5, 1978

TOTAL DEPTH: 4450'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 170 Sand and Clay	Ran 6 joints used 28#, 8 5/8" casing, 251.60' set at 263' K.B. with 225 sacks 60/40 Pozmix with 3 cc. Plug down at 1:30 PM, 3-27-78, by Howco.
170 - 384 Shale	
384 - 1050 Shale, Sand and Red Bed	
1050 - 1105 Red Bed	
1105 - 1124 Anhydrite	
1124 - 1785 Red Beds - Shale	
1785 - 4303 Lime and Shale	
4303 - 4327 Miss. Chert	
4327 - 4329 Lime	
4329 - 4400 Lime and Shale	
4400 - 4450 Cherty Lime and Shale	Ran 138 joints 4 1/2", 10.5# casing, 4440.74' pipe set at 4449' K.B. Cemented with 50 sacks Howco light cement, followed with 100 sacks Pozmix #1 with 18% salt and 3/4 of 1% CPR-2, and 1/8# flosel per sack and 1/8# tuffiber per sack and 5# gilsonite per sack with 250 gallons of mud flush ahead of cement. Plug down at 4:30 AM, 4-5-78, by Halliburton.



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Holl, F.G., Company L.L.C.
6427 East Kellogg
Wichita, KS 67207

April 27, 2000

MILLER #1-13
API 15-047-20352-00-00
330 S 2970 E
C SESESW 13-24S-17W
EDWARDS COUNTY

Dear Rob Long:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script that reads "David P. Williams".

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-8888