

Form CP-3
Rev. 6-26-62

16 KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 23 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Wichita Iron & Metal Corporation Inc.

Complete Address: Box 2421, Wichita, Kansas

Lease Name Campbell Well No. # 1

Location SE SE SW/4 Sec. 17 Twp. 27 Rge. 17 (E) (W) W

County Kiowa Total Depth 5071

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Glen & Smith Casing Pulling Co.

Address: 204 E. Sixth, Ellinwood, Kansas License No. 396

Operation Completed: Hour 2:15PM Day 21st Month Oct. Year 1963

The Above well was plugged as follows:

382' of 8 5/8" surface pipe, cemented with 400 sacks. 4767' of 5 1/2" long
string, cemented with 150 sacks. Top perferation 4675'. Plug was pushed
to 4625', bottom cemented with 5 sacks. Weight mud was pumped through
tubing, by Halliburton Cementing Co., to kill gas, before bottom of hole
was plugged and cemented. A plug was pushed to 275', 10' rock bridge,
hole was bailed down, and cemented with 25 sacks. Hole was filled with
mud to 40', 10' rock bridge, cemented with 10 sacks to base cellar.
3228' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 10/23/63
INV. NO. 9943-W

Signed: Archie Elving
Well Plugging Supervisor