

RECEIVED
STATE CORPORATION COMMISSION

KANSAS

FORM CP-3
Rev. 1-8-82

FEB 17 1982
CONSERVATION DIVISION
Wichita, Kansas

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-097-20,858-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Dunne-Gardner Petroleum Inc.

Complete Address 200 West Douglas Suite 250 Wichita Kansas 67202

Lease Name Thompson Well No. 1

Location C-5E-NE Sec. 21 Twp. 27 Rge. 17W (East)(West)

County Kiowa Total Depth 4825'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Dunne-Gardner Petroleum Inc.

Address _____ License No. _____

Operation Completed: Hour: 10:00AM Day: 16 Month: February Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

The anhydrite was topped at 1061'. 1st plug at 1050' with 50 sbs of cement. 2nd plug pushed rubber plug to 300' and pumped 35 sbs of cement on top of it. 3rd plug 40' to 0' with 10 sbs of cement on solid bridge. They also circulated 10 sbs of cement in rat hole & pumped 13 sbs of cement in water well. The cement used pumped thru drill pipe with hole full of heavy mud. The plugging was accomplished by Sun Cementing.

Amount of Surface Casing: 313' of 8 7/8" cement circulated with 225 sbs cement.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul Little
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: Paul Little
Conservation Division Agent

INVOICED

DATE 2-18-82
NO. 9452W