

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 25 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name U.S. Hydrocarbon Co.

Complete Address Box 11027 Washington St. Sta. Wichita, Ks

Lease Name Halper Well No. 2

Location 0 SW/SE Sec. 12 Twp. 27 Rge. 15 (E) (W) W

County Pratt Total Depth 4520

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Ralph Comstock Pipe Pulling Co. Inc.

Address Stafford, Ks License No. 490

Operation Completed: Hour 1:00 PM Day 21 Month 9 Year 1972

The above well was plugged as follows:

327 ft 8 5/8 surface pipe cement circulated. 4519 ft 4 1/2 long string
cemented with 250 sacks. Top perf. 4490 ft. Sand to 4450 ft, 4 sacks
cement with bailer. Pulled 2250 ft 4 1/2. Pump 2 sacks hulls, 15 sacks
gel, 100 sacks cement to surface.

Pumped by Globe Cementing Co. Great Bend, Ks

I hereby certify that the above well was plugged as herein stated.

Signed: A. Russell B. Hunter
Well Plugging Supervisor

INVOICED

DATE 9/28/72

INV. NO. 6367-11