

KANSAS

*24*  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 14 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Graham-Michaelis Drilling Co.

Complete Address: 211 N. Broadway, Wichita, Kansas 67202

Lease Name Plummer Well No. 1

Location App C SE Sec. 4 Twp. 27 Rge. 40 ~~(E)~~ (W)

County Stanton Total Depth 2286

Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A X

Other well as hereafter indicated: None

Plugging Contractor: Sargents Casing Pulling Co.

Address: Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 3:00PM Day 11 Month 7 Year 1969

The Above well was plugged as follows:

8 5/8" to 560' circulated w/ cement. 5 1/2" to 2279' cemented.

Open Hole 2279' to T.D. Plug bottom w/ 10 sacks cement.

Top of cement 2160' Mud 2160' to 560'

Spotted 45 sacks cement 560' to 430' Mud 430' to 45'

Plug, Halls & 15 sacks cement 45' to 0'. Company Pump

Pulled 1420' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edsall G. Evers  
Well Plugging Supervisor

DATE 7/14/69  
INV. NO. 85-W