

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-22627-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 14-6S-23W
2970 feet from S Section Line, 4950 feet from E Section Line
Lease Name: RICE Well #: 1
County: GRAHAM Total Vertical Depth: 3800 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3823		150 SX
SURF	8.625	241		185 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/12/2015 9:00 AM
Plug Co. License No.: 33771 Plug Co. Name: ULTIMATE WELL SERVICE, LLC
Proposal Rcvd. from: THOMAS ATKINS Company: RITCHIE EXPLORATION Phone: (785) 216-0155

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Port Collar at 2012' w/350 sx cement.
Perforations at 3605' - 3609'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/12/2015 12:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3700' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 2650' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 1250' and pumped 75 sx cement. Good circulation of cement. Pulled tubing out and topped off with 15 sx cement. Tied on to backside and squeezed with 20 sx cement. Shut in pressure 300 psi.

GPS: 39.53258 -099.86211

Perfs:

Top	Bot	Thru	Comments
3606	3610		
3605	3610		


Remarks: CONSOLIDATED TICKET # 49476

Plugged through: TBG

SEP 02 2015
CRM

District: 04

Signed _____



(TECHNICIAN)

CM

AUG 12 2015

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

AUG 21 2015

CONSERVATION DIVISION
WICHITA, KS