

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-22981-00-00
Spot: NESENWNE Sec/Twnshp/Rge: 18-8S-22W
970 feet from N Section Line, 1430 feet from E Section Line
Lease Name: RICE TRUST B Well #: 1-18
County: GRAHAM Total Vertical Depth: 3630 feet

Operator License No.: 3293
Op Name: RUSSELL OIL, INC.
Address: PO BOX 8050
EDMOND, OK 73083

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3628		120 SX
SURF	8.625	219		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/29/2015 9:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: TODD A. BROWN Company: RUSSELL OIL, INC. Phone: (785) 445-6270

Proposed Plugging Method: Ordered 375 sx 60/40 pozmix 4% gel cement, 12 sx gel and 400 # hulls.
Perforations at 3495' - 3498', 3533' - 3536'.
Port Collar set at 1782' w/200 sx cement to surface.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/29/2015 9:45 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Top down casing plug. Tied on to casing and pumped 50 sx cement w/200 # hulls; followed by 12 sx gel; followed by 180 sx cement. Casing full. Backside had cement to surface.
GPS: 39.36209 -09981361

Perfs:


Top	Bot	Thru	Comments
3533	3536		

Remarks: QUALITY OIL WELL CEMENTING TICKET # 1478

Plugged through: CSG

District: 04

Signed _____



(TECHNICIAN)
Received
KANSAS CORPORATION COMMISSION

CM

SEP 02 2015
CKM

AUG 03 2015

AUG 21 2015

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3