

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-153-21108-00-00  
Spot: NWNWSENV Sec/Twnshp/Rge: 2-4S-36W  
1340 feet from N Section Line, 1450 feet from W Section Line  
Lease Name: FISHER CATTLE CO Well #: 1-2  
County: RAWLINS Total Vertical Depth: 4929 feet

Operator License No.: 3882  
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN  
Address: 1515 WYNKOOP, STE 700  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4927		655 SX
SURF	8.625	260		200 SX

Well Type: SWD UIC Docket No: D32207.0 Date/Time to Plug: 07/30/2015 8:30 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BOOMER POMMEREHN Company: SAMUEL GARY JR. AND ASSOCIA Phone: (785) 421-7321

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement.  
8 5/8" surface casing set at 260' w/200 sx cement. 5 1/2" production casing set at 4927' w/655 sx cement. TD 4929', PBTD 4880'. Perforations: 4794' - 4814' (Mississippian). 2 7/8" Seal-Tite tubing parted at 13', 858' and 2873'. 2873' tubing recovered. Hole in 5 1/2" casing near 2873'. Junk in hole from 2873' to 4780'. Arrowset 1X packer at 4780'. All attempts to fish tubing from 5 1/2" casing below 2873' failed. Operator decided to plug.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/30/2015 12:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Set 5 1/2" cement retainer at 2769'. Ran tubing to 2767' and tested retainer. Stung into retainer. Pressured annulus to 500 psi. Pumped 140 sx cement at 700 psi. Pulled out of retainer to 2767' and pumped 185 sx cement. Cement circulated to surface. Pulled tubing to surface and topped off 5 1/2" casing w/30 sx cement. Visible cement in 8 5/8" casing.

GPS: 39.73856N -101.33006W

Perfs:

Top	Bot	Thru	Comments
4794	4814		

Remarks: QUALITY OILWELL SERVICES TICKET # 1479

Plugged through: TBG

SEP 02 2015

District: 04

Signed Darrel Dipman

(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

CKM

CM

AUG 03 2015

AUG 21 2015

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

uic