

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-033-21682-01-00
Spot: N2N2NENW Sec/Twnshp/Rge: 36-31S-19W
5099 feet from S Section Line, 3274 feet from E Section Line
Lease Name: SADIE 3119 Well #: 1-36H
County: COMANCHE Total Vertical Depth: 5227 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5100		WITH 50 SX CMT
COND 20		128		WITH 15 SX CMT
I1 7		5624	324	WITH 220 SX CMT
L1 4.5		9578		WITH 470 SX CMT
SURF 9.625		964		WITH 640 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/14/2015 10:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: STEVE JOHNSON Company: CRESCENT CONSULTING Phone: (405) 429-5000

Proposed Plugging Method: CIBP @ 5100' WITH 50 SX CMT. PLUG AT 1064' WITH 100 SX CMT. PLUG AT 400' WITH 60 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/14/2015 11:00 AM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

****SHOT 7" CASING AT 1306'. ONLY RECOVERED 324'. PIPE WOULDN'T GO THROUGH THE 9 5/8" SURFACE PIPE. ** CIBP @ 5100' WITH 50 SX CMT. 7" CASING SET AT 984'. CIRCULATED CMT TO SURFACE WITH 260 SX CLASS C CEMENT WITH 2% CC. CMT DID CIRCULATE. HOLE STAYED FULL. GOOD CIRCULATION THROUGHOUT JOB.**

Perfs:

Top	Bot	Thru	Comments
8300	8637		
7853	8100		
7498	7799		
6992	7220		
6644	6920		
6208	6550		
5880	6130		
5368	9475		

KCC WICHITA
AUG 26 2015
RECEIVED

Remarks: USED CLASS C CEMENT WITH 2% CC BY ORR ENTERPRISES. TMD= 9578'.

Plugged through: CSG

District: 01

RECEIVED
AUG 20 2015
KCC DODGE CITY

Signed _____

(TECHNICIAN)

SEP 02 2015
CKM