

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-077-22041-01-00
Spot: SWNENWNE Sec/Twnshp/Rge: 10-34S-5W
350 feet from N Section Line, 1740 feet from E Section Line
Lease Name: MILLER 3405 Well #: 2-3H
County: HARPER Total Vertical Depth: 4521 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4800		
COND	20	90		10 SX
	11 7	5295		465 SX
PROD	4.5	4521		0 SX
SURF	9.625	569		360 SX
	T1 4.5	8982		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/24/2015 12:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: STEVE JOHNSON Company: SANDRIDGE EXPL Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 08/24/2015 7:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

SET CIBP @ 4800' & CAPPED WITH 5 SKS CEMENT. RAN TUBING TO CIBP & CIRCULATED MUD TO SURFACE. LAYED DOWN TUBING & SHOT 7" CASING AT 1077'. CASING STUCK IN HOLE. PUMPED 150 SKS CEMENT OUT. SHOT AT 1077' TAGGED AT 930'. SHOT CASING AT 651', PULLED & LAYED OUT. RAN TUBING TO 628' & PUMPED 510 SXS CEMENT. PULL TO 251' & CIRCULATED WITH 100 SXS CEMENT.

Perfs:

Top	Bot	Thru	Comments
8872	8874	CSG	
8653	8655	CSG	
8494	8496	CSG	
8306	8308	CSG	
8121	8123	CSG	
7930	7932	CSG	
7746	7748	CSG	
7556	7558	CSG	
7368	7370	CSG	
7184	7186	CSG	
6994	6996	CSG	
6802	6804	CSG	
6618	6620	CSG	
6427	6429	CSG	
6239	6241	CSG	
6050	6052	CSG	
5859	5861	CSG	
5673	5675	CSG	
5490	5492	CSG	
5348	8874	CSG	

Remarks: TMD = 8985

Plugged through: TBG

KCC WICHITA

AUG 28 2015

RECEIVED

SEP 02 2015
CKM

District: 02

Signed _____

(TECHNICIAN)

JK