

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-145-21806-00-00
Spot: E2SESWSW Sec/Twnshp/Rge: 8-22S-16W
330 feet from S Section Line, 1318 feet from W Section Line
Lease Name: JESSIE Well #: #1-8
County: PAWNEE Total Vertical Depth: 4025 feet

Operator License No.: 31725
Op Name: SHELBY RESOURCES LLC
Address: 621 17TH ST STE 1155
DENVER, CO 80293

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1036		WITH 450 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/12/2015 2:00 PM
Plug Co. License No.: 5142 Plug Co. Name: STERLING DRILLING COMPANY
Proposal Rcvd. from: LANNY SALOGA Company: STERLING DRILLING COMPANY Phone: (620) 672-9508

Proposed Plugging Method: 1ST PLUG AT 3936' WITH 50 SX CMT. 2ND PLUG AT 1060' WITH 50 SX CMT. 3RD PLUG AT 400' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: NONE
Date/Time Plugging Completed: 08/12/2015 5:45 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

1ST PLUG AT 3936' WITH 50 SX CMT. 2ND PLUG AT 1060' WITH 50 SX CMT. 3RD PLUG AT 400' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY QUALITY OIL WELL.

Plugged through: DP

District: 01

Signed

SA

(TECHNICIAN)

KCC WICHITA

AUG 26 2015 Form CP-2/3

RECEIVED

RECEIVED
AUG 24 2015
KCC DODGE CITY

9/3/15 ckm