

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-01147-00-02
Spot: NENESE Sec/Twnshp/Rge: 36-6S-20W
2019 feet from S Section Line, 646 feet from E Section Line
Lease Name: VEHIGE OWWO Well #: 2-SWD
County: ROOKS Total Vertical Depth: 1652 feet

Operator License No.: 5399
Op Name: TREK AEC, LLC
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
LI	2.875	1239		175
PROD	4.5	1527		400 sx
SURF	8.625	161		100 SX

Well Type: SWD UIC Docket No: D19910.0 Date/Time to Plug: 08/11/2015 10:30 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: TANNER NELSON Company: TREK AEC LLC Phone: (620) 755-2571

Proposed Plugging Method: Ordered 180 sx 60/40 pozmix 4% gel cement w/100 # hulls.
2 7/8" tubing cemented in 4 1/2" casing.
Inj. Perforations at 1292' - 1392'.

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/11/2015 12:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 2 7/8" tubing and pumped 180 sx cement w/100 # hulls. Maximum pressure 150 psi. Shut in pressure 50 psi. Visually checked 8 5/8" x 4 1/2" annulus. Cement to surface.
GPS: 39.48662N -09948278W

Perfs:

Top	Bot	Thru	Comments
1292	1392		

Remarks: SWIFT SERVICES TICKET # 28725

Plugged through: TBG

9/3/15 ckm

District: 04

Signed Pat Bedore
(TECHNICIAN) CM

AUG 12 2015

Received
KANSAS CORPORATION COMMISSION
AUG 21 2015
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

✓ UIC