

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-22011-00-00
Spot: W2SE Sec/Twnshp/Rge: 15-8S-18W
1320 feet from S Section Line, 1980 feet from E Section Line
Lease Name: PETTYJOHN Well #: 2
County: ROOKS Total Vertical Depth: 3460 feet

Operator License No.: 5399
Op Name: TREK AEC, LLC
Address: 155 N MARKET STE 710
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5.5 | 3450 | | 130 SX |
| SURF | 8.625 | 182 | | 130 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/10/2015 9:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: TANNER NELSON Company: TREK AEC LLC Phone: (620) 755-2571

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/800 # hulls.
DV Tool at 1354'.
Production perforations at 3231' - 3349'.
Tubing and bit stuck in hole at 1680'

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/11/2015 9:40 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing, tagged tubing in hole at 1690'. Pulled tubing up to 1680' and pumped 175 sx cement w/200 # hulls. Pulled tubing to 1200' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 800' and pumped 80 sx cement w/100 # hulls. Pulled tubing to 400' and pumped 95 sx cement w/100 # hulls. No circulation. Well went on vacuum. Pulled all tubing.
08/11/2015- Ran tubing and tagged TOC at 320'. Pulled tubing to 300' and pumped 50 sx cement to circulate cement to surface. Pulled all tubing. Topped off 5 1/2" casing with 5 sx cement. Checked 8 5/8" x 5 1/2" annulus and cement was to surface.

GPS: 39.35392N -099.31367W

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3231 | 3349 | | |

Remarks: SWIFT SERVICES TICKET # 28723 AND 28724

Plugged through: TBG

9/3/15ckm

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

AUG 12 2015

AUG 21 2015

CONSERVATION DIVISION
WICHITA, KS