

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-155-30030-00-00  
Spot: NE Sec/Twnshp/Rge: 23-25S-8W  
4620 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: KREHBIEL Well #: 2  
County: RENO Total Vertical Depth: 4423 feet

Operator License No.: 5822  
Op Name: VAL ENERGY, INC.  
Address: 125 N MARKET ST STE 1710  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	4220		150 SX
SURF	10.75	252		100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/27/2015 12:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DION HOWARD Company: QUALITY WELL SERVICE Phone: (316) 263-6688

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 07/29/2015 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET CIBP @ 3470' CAPPED WITH 2 SX CEMENT ON TOP. PERFORATED CASING WITH 4 SHOTS @ 1200', 650' & 300'. TRIPPED IN TUBING TO 1200' SPOTTED 50 SX OF CLASS A WITH 3% CC. CEMENT. WAITED 2 HOURS TRIED TO TAG, DISPLACING LOTS OF OIL, TRIED TO TAG 1.5 HOURS LATER STILL WOULD NOT TAG UP, AGREED TO LET STAND OVERNITE, 7/27/2015. TAGGED UP AT 1000' ON 7/28/15, TRIPPED TUBING INTO 650' SPOTTED 50 SX OF CLASS A W/3% CC CEMENT. TRIPPED TUBING INTO 300' AND CIRCUALTED TO SURFACE WITH 225 SX CLASS A 3 % CC CEMENT, DISPLACING OIL UP UNTIL CEMENT CAME TO SURFACE INSIDE AND OUTSIDE OF 7". 7/29/15 CEMENT AT TOP OF 7" AND 10/75" CUT OFF 4' BELOW GROUND.

Perfs:

Remarks: QUALITY WELL SERVICE PROVIDED CEMENT FOR THE PLUG JOB. TICKET #6365. PAST 10 YEAR, NO TA OR LEASE. Commissioner order?

Plugged through: TBG

9/3/15 ckm

District: 02

Signed B. J. Hope

Received  
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

AUG 21 2015

CONSERVATION DIVISION  
WICHITA, KS