

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-187-21058-00-00
Spot: SWSE Sec/Twnshp/Rge: 1-30S-41W
781 feet from S Section Line, 1896 feet from E Section Line
Lease Name: DANIELS Well #: 1
County: STANTON Total Vertical Depth: 5581 feet

Operator License No.: 33856
Op Name: WHITE EXPLORATION, INC.
Address: 1635 N. WATERFRONT PKWY SUITE 1
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5420		WITH 2 SX CMT
DVT	5.5	3485		WITH 500 SX CMT
PROD	5.5	5578	0	WITH 200 SX CMT
SURF	8.625	1624		WITH 595 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/11/2015 11:00 AM
Plug Co. License No.: 31985 Plug Co. Name: GONZALES WELL SERVICE, INC
Proposal Rcvd. from: TERRY BAIRD Company: WHITE EXPLORATION Phone: (316) 641-8906

Proposed Plugging Method: Set CIBP @ 5420' and top with 2 sacks of cement. Fill hole to 1675' and Plug with 50 sacks @ 1675', 40 sacks @ 600' and 10 sacks @ 40'. Check backside.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/11/2015 2:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 5420' WITH 2 SX CMT. 1ST PLUG AT 1689' WITH 50 SX CMT. 2ND PLUG AT 590' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5470	5476		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY HURRICAN SERVICES.

Plugged through: CSG

District: 01

Signed

[Handwritten Signature]
SA

(TECHNICIAN) KCC WICHITA

RECEIVED
AUG 20 2015
KCC DODGE CITY

[Handwritten Initials]

9/3/15cpm
AUG 26 2015
RECEIVED

Form CP-2/3