

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-077-00265-00-01  
Spot: SWNWSE Sec/Twnshp/Rge: 7-33S-5W  
1650 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: FLOWERS Well #: 1  
County: HARPER Total Vertical Depth: 4854 feet

Operator License No.: 5044  
Op Name: WHITE PINE PETROLEUM CORPORATI  
Address: 110 S MAIN ST STE 500  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3659		400 SX
SURF	8.625	210		0 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/13/2015 12:00 PM  
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION  
Proposal Rcvd. from: MARK MORGANSTERN Company: CLARKE CORPORATION Phone: \_\_\_\_\_

Proposed Plugging Method: BP. 3420' & 2 SKS CEMENT. 35 SX @ 1050', 35 SX @ 700', CIRCULATE @ 260'.

Plugging Proposal Received By: DAN FOX WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/13/2015 12:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 3420' & CAPPED WITH 2 SKS CEMENT. THE CASING WAS RECOVERED & LAYED DOWN. TUBING WAS RUN TO 1073' SPOTTED 40 SKS CEMENT. PULL TUBING TO 689' SPOTTED 40 SXS CEMENT. PULL TUBING TO 270' & CIRCUALTED CEMENT TO SURFACE WITH 95 SKS.

Perfs:

Top	Bot	Thru	Comments
3473	3483		CSG

Remarks: COMMON 3% CACL. ALLIED CEMENTING

Plugged through: TBG

District: 02

Signed \_\_\_\_\_



(TECHNICIAN)

9/3/15 CKM

KCC WICHITA

AUG 28 2015

RECEIVED