

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-00276-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 12-22S-33W
2661 feet from S Section Line, 2620 feet from E Section Line
Lease Name: KISNER - A Well #: 1
County: FINNEY Total Vertical Depth: 2722 feet

Operator License No.: 33701
Op Name: XOG OPERATING, LLC
Address: PO BOX 352
MIDLAND, TX 79702

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2657		
PROD 7		2718	0	WITH 900 SX CMT
SURF 10.75		514		WITH 375 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/11/2015 8:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: REUBEN Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/11/2015 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 70 SX CMT AT 1900'. TAG TOP OF PLUG AT 1891'. (BOTTOM OF PLUG APPROXIMATELY 2300'). FILL CASING WITH WATER & TEST TO 500#. HOLDING. RAN CBL FROM 1700' TO 0'. HAVE CMT AT 1500', THEN QUESTIONABLE UP TO 1090', THEN CMT UP TO 740'. CASING SHOE NOT COVERED WITH CMT. PERFORATE AT 525'. RUN TBG TO 1200' & SPOT 50 SX CMT. TOO H W/TBG. CIRCULATE CMT THROUGH PERFS AT 525' TO SURFACE WITH 230 SX CMT. TOP OFF WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2672	2684		
2617	2644		

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed

Ken Jehlik
SA
(TECHNICIAN)

9/3/15

RECEIVED
AUG 20 2015
KCC DODGE CITY

KCC WICHITA

AUG 26 2015

RECEIVED

Form CP-2/3