

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-207-29211-00-00
Spot: SESESENE Sec/Twnshp/Rge: 24-26S-16E
2475 feet from N Section Line, 165 feet from E Section Line
Lease Name: NOEL JACKSON Well #: 1-24
County: WOODSON Total Vertical Depth: 1068 feet

Operator License No.: 34243
Op Name: KING, CHARLES DBA CK OIL
Address: 409 E. WILSON
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	40		12 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/09/2015 12:00 AM
Plug Co. License No.: 34953 Plug Co. Name: KING, ANDREW D.
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed
Plugging
Method:

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 02/09/2015 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran drill pipe in and washed down to TD of 1068'. Mixed and pumped gel down drill pipe, mixed cement and pumped cement through drill pipe at TD and placed a 100' plug. Pulled pipe up to the Kansas City formation. Pumped cement through drill pipe and placed a 75' plug at the base of the Kansas City. Pulled pipe up to 250' and pumped and circulated cement through the drill pipe from 250' to surface. Pulled drill pipe out and topped off well with cement. A total of 90 sacks of portland cement was reported used to plug this well.

Perfs:

RECEIVED
KCC DIST # 3
AUG 25 2015
CHANUTE, KS

RD

Remarks:

Plugged through: DP

SEP 02 2015
CKM

District: 03

Signed _____

(TECHNICIAN)

KCC WICHITA

AUG 28 2015

RECEIVED