

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-151-21346-00-00  
Spot: W2SEW Sec/Twnshp/Rge: 36-28S-11W  
1980 feet from N Section Line, 1500 feet from W Section Line  
Lease Name: KOG ALLBRITTEN Well #: 1-36  
County: PRATT Total Vertical Depth: 2898 feet

Operator License No.: 3842  
Op Name: LARSON ENGINEERING, INC. DBA LAR  
Address: 562 W STATE RD 4  
OLMITZ, KS 67564

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2897	1640	WITH 200 SX CMT
SURF	8.625	350		WITH 325 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/11/2015 12:30 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 25 SX CMT WITH 150# HULLS. PLUG AT 720' WITH 10 SX GEL & 50 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE  
Date/Time Plugging Completed: 08/11/2015 3:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMP 30 SX CMT WITH 100# HULLS AT 2500'. 1ST PLUG AT 720' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2650	2655		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: CSG

SEP 02 2015  
CKM

District: 01

Signed



(TECHNICIAN)  
KCC WICHITA

SA

RECEIVED  
AUG 21 2015  
KCC DODGE CITY

AUG 26 2015  
RECEIVED

Form CP-2/3